

SURVEY & REMONUMENTATION

APR 29 1995

RECEIVED FOR RECORD

COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970
1995 REMONUMENTATION PROGRAM

95 DEC 13 AM 9:00

LIBER NO. 5 PAGE NO. 320

Melissa DeVough

REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

For corners in RICH TWP.
LAPEER
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>10N</u> R <u>10E</u>	M-8	
	T _____ R _____		
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____


I, JONATHAN M. FIELD, in a field survey on MARCH 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1833 GLO; PARKE, D.S.; SET POST; SUGAR 12 S26 1/2W 30 1/2LKS., BEECH 10 N7W 20LKS.
1986 GRAVLIN, P.S.#23510; SURVEY L.7, PG.446; SET 1/2" IRON; EAST 17.86' 8" ASH, S20E 21.95' 8" HICKORY, N40E 10.16' 6" ASH
1989 GRAVLIN, P.S.#23510; LCRC L.4, PG.259; SET 1/2" IRON; SAME WITS AS 1986 SURVEY ABOVE
1995 GRAVLIN, P.S.#23510; SURVEY L.10, PG.847; FND 1/2" IRON; S20E 21.95' 8" HICKORY, N40E 10.16' 6" ASH, N40E 3.04' 6" ASH, N85W 22.6' 8" ASH

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1995 ROWE ENG.; FIELD, P.S.#37276; FND 1/2" ROD AT N. FACE OF FALLEN 12" FENCE CORNER POST ALSO FND 4 WITS GIVEN BY GRAVLIN IN 1986 INDICATING THAT FND IRON IS IN SAME POSITION
G.L.O. NOTES FOR T9N-R11E IMPLY THAT THIS CORNER IS COMMON WITH A S. T10N-R11E CORNER

APPROVED AND
 PEER GROUP
 PAGES OF 1990
 LAPEER COUNTY

 RAY DAVIS P.S. CO. SURVEYOR
 DATE 7-13-95

M-8 TO M-9 2657.08' (GRAVLIN 1995)
 M-8 TO M-7 2647.43' (GRAVLIN 1986)

ACCEPTED FND 1/2" ROD AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-8 SET STANDARD BRASS CAP ON FND 1/2" ROD
N40°E, 3.11' SET NAIL W/REMON TAG BELOW FND NAIL W/FLAG. IN SE FACE 6" ASH
N40°E, 10.20' SET NAIL W/REMON TAG BELOW FND NAIL W/FLAG. IN NW FACE 6" ASH
S80°E, 17.76' SET NAIL W/REMON TAG IN TOP OF 10" ASH STUMP
S20°E, 22.04' SET NAIL W/REMON TAG BELOW FND NAIL W/FLAG. IN E. FACE 10" OAK
N85°W, 22.64' SET NAIL W/REMON TAG BELOW FND NAIL W/FLAG. IN S. FACE 8" ASH

Signed by *Jonathan M. Field* Date 12-1-95
 Surveyor's Michigan License No. 37276

