

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970
1995 REMONUMENTATION PROGRAM

RECEIVED FOR RECORD

95 DEC 13 AM 9:01

LIBER NO. 5 PAGE NO. 321
Nelson DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

For corners in RICH TWP.
LAPEER
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>10E</u>	<u>M-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on MARCH 19 95
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1833 GLO; PARKE, D.S.; SET POST; PINE 12 S29W 22LKS., HEMLOCK NO SIZE 5LRS.
 1906 SICKLESTEEL, C.S.; SURVEY OF SEC.25; NO OBJECT STATED, NO WITS GIVEN
 ??? LAPEER CO. RD. COMM.; WIT BOOK #5; NO OBJECT STATED; NE 46.67' IRON, SE 46.67' IRON, SW 46.67' IRON, NW 46.67' IRON
 1983 GRAVLIN, P.S.#23510; SURVEY L.6 PG.507; SET NAIL FROM OLD WITS; S60E 59.02' 6" ELM, S45E 46.74' 3/4" IRON, S45W 46.74' 3/4" IRON, N45W 48.43' 3/4" IRON, N60W 74.10' PHONE BOX
 1983 GRAVLIN, P.S.#23510; SURVEY L.6, PG.508; SET NAIL FROM OLD WITS; SAME WITS AS 1983 ABOVE
 1989 GRAVLIN, P.S.#23510; LCRC L.4, PG.259; SET NAIL FROM OLD WITS; SAME AS 1983 SURVEY ABOVE
 1993 GRAVLIN, P.S.#23510; SURVEY L.10, PG.154; FND P-K NAIL; SAME WITS AS 1983 SURVEY ABOVE
 1995 GRAVLIN, P.S.#23510; SURVEY L.10, PG.847; FND P-K NAIL; SAME WITS AS 1983 SURVEY ABOVE
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1995 ROWE ENG.; FIELD, P.S.#37276; FND P-K NAIL 0.4' N. OF C/L ASPH. ROAD E-W AND INLINE WITH TREE/BRUSH ROW N-S FND P-K NAIL IN ELM SE AS GIVEN BY GRAVLIN IN 1983 INDICATING THAT FND P-K NAIL AT CORNER IS IN SAME POSITION AS SET BY GRAVLIN IN 1986


G.L.O. NOTES FOR T9N-R11E INDICATE THAT THIS CORNER IS COMMON WITH A-9 T10N-R11E

M-9 TO M-10 2660.64' (REI 1995)	
2660.53' (GRAVLIN 1993)	M-9 TO M-7 5304.51 (GRAVLIN)
M-9 TO M-8 2657.08' (GRAVLIN 1995)	M-9 TO M-9 5304.44 (REI 1995)

ACCEPTED FND P-K NAIL AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 M-9 SET 1/2"X 18" ROD W/ STANDARD BRASS CAP IN MON. BOX
 S60°E, 58.94' FND P-K NAIL IN SW FACE 10" ELM
 S70°W, 104.60' SET NAIL W/REMON TAG IN SE FACE 12" ELM
 S45°E, 36.50' SET CHIS. NOTCH IN TOP W. END 12" STEEL CONCRETE APPROVED LAND CORNER
 N65°W, 116.12' FND P-K NAIL IN S. FACE P. POLE PA 345 OF 1990
 N70°W, 75.30' TOP CENTER OF PHONE RISER LAPEER COUNTY
- NORTH, 2.00' SET P-K NAIL
 EAST, 2.00' SET P-K NAIL

RAY DAVIS, P.S. CO. SURVEYOR
DATE 7-13-95



Signed by *Jonathan M. Field* Date 12-1-95
 Surveyor's Michigan License No. 37276