

SURVEY &
REMONUMENTATION

1993

COMMISSION

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>LAPEER</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10</u> NR <u>10</u> E	<u>M-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORD

96 JAN -11 PM 12:58
LIBER 005 PAGE 68
Michigan State Board of Land Surveyors
RECEIVED
LAND SURVEYOR

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Jonathan M. Field, in a field survey on October, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1833 GLO- Parke, D.S.; Set 1/2 mile post; Maple 24" N22W 41 lks., Lynn 11" S36W 39lks.
1906 Sickledsted, C.S.; Stake, Elm 22" N56W 58lks., Swamp Oak 12" S44W 108lks.
1993 Gravlin, P.S.#23510; Survey (unrecorded) Job No. 93131, set iron at split of mile dist.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Rowe Eng.- Field, P.S.#37276; Fnd. 1/2" rod w/cap #23510 4'S of c/l gravel road E-W and on fence/tree line N-S
Fnd. 3 previous wits which verify that rod is in same position as 1993 Gravlin survey
Accepted 1/2" rod w/cap as best evidence of original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10 1/2" rod w/ standard brass cap
N55°W, 56.94' Set nail w/remon tag in SW face 8" Oak
N03°E, 32.39' Set nail w/remon tag above fnd nail w/flag. in W. face 16" Oak
S35°E, 36.32' Set nail w/remon tag above fnd nail w/flag. in W. face 6" Oak
S17°W, 44.18' Set nail w/remon tag above fnd nail w/flag. in E. face 34" Oak
S47°W, 45.84' Set nail w/remon tag in NW face 6" Ash

JONATHAN
M. FIELD
LAND
SURVEYOR
No.
37276

Signed by Jonathan M Field
Surveyor's Michigan License No. 37276

Date 11-24-93