

SURVEY &  
REMONUMENTATION

1993

COMMISSION

REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>LAPEER</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10</u> N R <u>10</u> E	<u>M-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORD

94 JAN - 6 PM 59  
LIBER 005 PAGE 69  
Michigan State Board of Land Surveyors  
RECORDS SECTION  
LANSING, MICHIGAN

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Jonathan M. Field, in a field survey on October, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 1833 GLO- Parke, D.S.; Set post; B.Ash 14" S19W 33lks., B.Ash 9" N28E 37lks.  
 1906 Sickledsted, C.S.; Stake, Swamp Oak 22" N13½W 43lks., Swamp Oak (no size) S61E 18lks.  
 1993 Gravlin, P.S.#23510; Survey (unrecorded) Job No. 93131, Fnd. pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 1993 Rowe Eng.- Field, P.S.#37276; Fnd. 1/2" pipe on c/l gravel road E-W and on fence/tree line N-S  
 Fnd. 3 previous wits which verify that pipe is in same position as 1993 Gravlin survey  
 Accepted 1/2" pipe as best evidence of original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 M-11 1/2" rod w/ standard brass cap  
 N62°E, 41.04' Set nail w/remon tag in NW face 6" Elm  
 N06°W, 29.91' Set nail w/remon tag in W. face 6" Elm  
 S45°W, 42.94' Set nail w/remon tag above fnd nail w/flag. in E. face 18" Ash  
 S03°E, 24.51' Set nail w/remon tag above fnd nail w/flag. in E. face fence corner post  
 S41°E, 32.34' Set nail w/remon tag in NE face 38" Oak  
 N50°W, 25.49' Set nail w/remon tag above fnd nail w/flag. in SW face 8" Elm

Signed by Jonathan M Field  
 Surveyor's Michigan License No. 37276

Date 11-24-93

