

SURVEY &
REMONUMENTATION

1993

COMMISSION

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

For corners in

| | | |
|---------------------------------------|----------------------------|---------------|
| <u>LAPEER</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>10</u> NR <u>10</u> E | <u>M-13</u> |
| | T _____ R _____ | |
| | T _____ R _____ | |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | <u>Fig. 1</u> |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

94 JAN -6 PM 1:02
LIBER 005 PAGE 71
Michael Miles
RECORDS CLERK
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 8 | 9 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Jonathan M. Field, in a field survey on October, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1833 GLO- Parke, D.S.; Set post; Maple 16" S26W 521ks., Beech 12" N63E 371ks.
1987 Elrich, P.S.#18986; Survey L.7, Pg.718 - Fnd. 1/2" iron
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1993 Rowe Eng.- Field, P.S.#37276; Fnd. 1/2" rod 1'S of c/l gravel road E-W and on fence/tree line N-S; Also fnd 3/4" pipe N24°W, 4.34' from 1/2" rod
Fnd. 3 previous wits which verify that 1/2" rod is in same position as 1987 survey Accepted 1/2" rod as best evidence of original corner position.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-13 1/2" rod w/ standard brass cap
S63°E, 77.94' Set nail w/remon tag in NE face cut-off T. pole
S48°E, 42.61' Set nail w/remon tag in SW face 26" Maple also fnd nail w/flag. in W. face at 42.10'
S02°W, 23.87' Set nail w/remon tag in W. face 14" Ash also fnd nail w/flag. in N. face at 23.0'
N06°W, 25.99' Set nail w/remon tag in E. face 10" Ash
N47°W, 35.49' Set nail w/remon tag in SW face 30" Maple
S05°W, 19.54' Fnd. 1 1/2" pipe
N24°W, 4.34' Fnd. 3/4" pipe

Signed by Jonathan M. Field Date 11-24-93
Surveyor's Michigan License No. 37276 LIBER 005 PAGE 71
FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JUN. 25, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

