

SURVEY & REMONUMENTATION

MAR 13 1998

SECTION

**1997 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
97 NOV 12 PM 2:53

For corners in: **RICH TWP.**

LAPEER

(County)

Located In:

Corner Code #

1. Public Land Survey

T 10N R 10E

M-13

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on JUNE 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1833 GLO; PARKE, D.S.; SET POST; MAPLE 16 S26W 52LKS., BEECH 12 N63E 37LKS.
1971 KAY ENG.; KAY, P.S.#14096; SURVEY; L.001,PG.043; 1/2" IRON; N60W 34.6' 24" MAPLE, S45E 42.1' 20" MAPLE, S45W 38.2' 24" MAPLE
1975 SMITH SURVEYING; SMITH, P.S.#21582; SURVEY; L.003,PG.432-433; FND. IRON; NO WITS GIVEN
1978 BECK-GRAVLIN; GRAVLIN, P.S.#23510; SURVEY L.004,PG.676; NO OBJECT STATED; N60W 34.74' NAIL IN 24" MAPLE, S45E 42.10' NAIL IN 20" MAPLE, SOUTH 23.00' NAIL IN 16" ASH
1987 HENDERSON-BATE; ELRICH, P.S.#18986; SURVEY; L.007,PG.718; FND. 1/2" IRON; SAME WITS AS 1978 SURVEY
1988 GRAVLIN, P.S.#23510; SURVEY; L.007,PG.885; FND. 1/2" IRON; SAME WITS AS 1978 SURVEY ABOVE
1993 FIELD, P.S.#37276; 1993 REMON LCRC FOR M-13 T10N-R10E; FND. 1/2" ROD
M-1 TO L-1 2642.52' GRAVLIN '88 & '78; SMITH '75

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1997 ROWE; FIELD, PS#37276; FND. 1/2" W/ STANDARD REMON CAP RECOVERED ALL 1993 REMON WITS CITED ABOVE

NOTE: THIS CORNER IS COMMON WITH M-1 T9N-R10E, A-13 T10N-R11E, AND A-1 T9N-R11E

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-13 1/2" ROD W/ STANDARD REMON CAP
S63°E, 77.94' NAIL W/ REMON TAG IN NE FACE CUT-OFF T.POLE
S48°E, 42.61' NAIL W/ REMON TAG IN SW FACE 26" MAPLE
S02°W, 23.87' NAIL W/ REMON TAG IN W. FACE 14" ASH
N06°W, 25.99' NAIL W/ REMON TAG IN E. FACE 10" ASH
N47°W, 35.49' NAIL W/ REMON TAG IN SW FACE 30" MAPLE

DEED GROUP
RECORDED LAND CORNER
RECORDED OF 1990
LAPEER COUNTY
[Signature]
KAY ENGINEERING CO. SURVEYOR
9-29-97



Signed by *Jonathan M. Field* Date 11-11-97
Surveyor's Michigan License No. 37278

LIBER 0005 PAGE 0451