

SURVEY & REMONUMENTATION

MAR 13 1998

SECTION

1997 REMONUMENTATION PROGRAM LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in: BURLINGTON TWP.

Form with columns: LAPEER (County), Located In, Corner Code #. Includes sections for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

RECEIVED FOR RECORD

97 NOV 12 PM 2: 54

Melissa De Vaughn REGISTER OF DEEDS LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

I, JONATHAN M. FIELD, in a field survey on JUNE 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: 1833 GLO; PARKE, D.S.; SET POST; MAPLE 16 S26W 52LKS., BEECH 12 N63E 37LKS. 1971 KAY ENG.; KAY, P.S.#14096; SURVEY; L.001,PG.043; 1/2" IRON; N60W 34.6' 24" MAPLE, S45E 42.1' 20" MAPLE, S45W 38.2' 24" MAPLE 1975 SMITH SURVEYING; SMITH, P.S.#21582; SURVEY; L.003,PG.432-433; FND. IRON; NO WITS GIVEN 1978 BECK-GRAVLIN; GRAVLIN, P.S.#23510; SURVEY L.004,PG.676; NO OBJECT STATED; N60W 34.74' NAIL IN 24" MAPLE, S45E 42.10' NAIL IN 20" MAPLE, SOUTH 23.00' NAIL IN 16" ASH 1987 HENDERSON-BATE; ELRICH, P.S.#18986; SURVEY; L.007,PG.718; FND. 1/2" IRON; SAME WITS AS 1978 SURVEY 1988 GRAVLIN, P.S.#23510; SURVEY; L.007,PG.885; FND. 1/2" IRON; SAME WITS AS 1978 SURVEY ABOVE 1993 FIELD, P.S.#37276; 1993 REMON LCRC FOR M-13 T10N-R10E; FND. 1/2" ROD

M-1 TO L-1 2642.52' GRAVLIN '88 & '78; SMITH '75

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 1997 ROWE; FIELD, PS#37276; FND. 1/2" W/ STANDARD REMON CAP RECOVERED ALL 1993 REMON WITS CITED ABOVE

NOTE: THIS CORNER IS COMMON WITH M-1 T9N-R10E, M-13 T10N-R10E, AND A-1 T9N-R11E

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13 1/2" ROD W/ STANDARD REMON CAP S63°E, 77.94' NAIL W/ REMON TAG IN NE FACE CUT-OFF T. POLE S48°E, 42.61' NAIL W/ REMON TAG IN SW FACE 26" MAPLE S02°W, 23.87' NAIL W/ REMON TAG IN W. FACE 14" ASH N06°W, 25.99' NAIL W/ REMON TAG IN E. FACE 10" ASH N47°W, 35.49' NAIL W/ REMON TAG IN SW FACE 30" MAPLE



Signed by Jonathan M. Field Surveyor's Michigan License No. 37276

APPROVED Date 11-11-97

LIBER 0005 PAGE 0452

RAY DAVIS P.S. CO. SURVEYOR DATE 9-29-97