

**SURVEY & REMONUMENTATION**

OCT 29 1996

COMMISSION

REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED RECORD  
96 SEP 30 PM 3:15

For corners in

<u>LAPEER</u> <small>(County)</small>	Located In:	Corner Code #	
	10N 11E	G-13	
1. Public Land Survey	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

*Richard T. Smith*  
REGISTER OF DEEDS  
LAPEER COUNTY MICHIGAN

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, EARL E. GRAVLIN AUGUST 96

in a field survey on \_\_\_\_\_, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

History: Parke, 1833, Cor. Sections 33, 34 B. Ash 24 inches diamer cor. tree. County Surveyor Bates May 1867 Book 2, Page 143, Stone 14.11.7 Small Stones, plow point. Jog, 4.13 CH (272.58'). Act 74 none. Recorded Surveys Gravlin Land Survey, Liber 11, Page 304, found RR spike no witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

GRAVEL ROAD EAST AND WEST, GRAVEL ROAD NORTH, FOUND RR SPIKE G-13 TO H-13 2650.89 AND G-13 TO G-1 270.71

PEER GROUP  
APPROVED LAND CORNER  
PA 345 OF 1990  
LAPEER COUNTY

*Ray Davis*  
RAY DAVIS P.S. CO. SURVEYOR  
DATE 9-10-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13, SOUTHWEST CORNER SECTION 34, T10N-R11E  
FOUND RR SPIKE REPLACED WITH 1/2" IRON AND BRASS CAP  
S20°W 29.14' NAIL AND TAG W/S 10" ASH  
N05°W 17.45' EAST LEG SIGN  
N35°E 45.20' NAIL AND TAG E/S 24" ASH  
N70°W 48.62' FACE CABLE SIGN



Signed by *Earl E. Gravlin* Date 9-10-96  
Surveyor's Michigan License No. 23510