

# SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

REMONUMENTATION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Lapeer</u> <small>(County)</small>	Located In:	Corner Code <u>##</u>
1. Public Land Survey	T <u>10N</u> R <u>11E</u>	<u>M-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORD  
94 DEC 14 AM 10:44  
LIBER NO. 005 PAGE NO. 136  
*Melissa De Vaughn*  
REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN  
Register of Deeds Stamp & File Number

I, Earl E. Gravlin, in a field survey on September, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Parke 1833 Blaze on Pine 34", marked 1/4, No other ties. ACT 74 FORMS\_L 2, P 535, Swarts 3-21-74, 1/2" Iron over stone, Fence post W 26.0', Large stone, East 19.0', West end culvert, N 25° W 63.0' ACT 132 FORMS\_L 2, P 641, Swarts 10-23-73, same as L 2, P 535.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Gravel Road Fence line to West, Nothing to East. Found 1/2" Iron, 2.5' West C/L gravel road. M-6 to M-5 2654.08', M-6 to M-7 2654.50'

PEER GROUP  
APPROVED LAND CORNER  
PA 345 OF 1990  
LAPEER COUNTY

*Ray Davis*  
RAY DAVIS P.S. CO. SURVEYOR.  
DATE 12-14-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

November 7, 1994  
Found 1/2" Iron, 2.5' West C/L gravel road, Set Brass Cap  
N 21° W 119.56' NAIL AND TAG E/S 15" ELM  
WEST 46.87' NAIL AND TAG S/S 10" ELM  
S 18° 29' E 180.68' NAIL AND TAG W/S POWER POLE  
N 28° 48' E 119.68 NAIL AND TAG W/S POWER POLE



Signed by *Earl E. Gravlin* Date 12/13/94  
Surveyor's Michigan License No. 23510