

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Lapeer</u> <small>(County)</small>	Located In:	Corner Code ##
1. Public Land Survey	T <u>10N</u> R <u>11E</u>	<u>M-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD

94 DEC 14 AM 10:47

LIBER NO. 005 PAGE NO. 159

Melissa DeLoach
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	3	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Earl E. Gravlin, in a field survey on September, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recoverec, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Parke, 1833 P 488, Set Stake, Hemlock 11 S13W 34, Hemlock 9 N 3.5W 35 Burnham 1834, intersected 7 jks NORTH (4.62) Hemlock 14 S56E 28, Maple 12 N 29E 29 ACT 74 FORMS L 2, P 535, 1/2" Iron S 85° W 27.8' Fence Corner Post, EAST 23.5' Fence Corner Post, N 10° W 53.3' 16" Aspen, Swartz, 3-21-74, L 3, Page 48 Kennedy 7-10-78 Job # 78-1138, East 24.55' Fence Post, N 70° E 34.04' Fence Post, N 50° W 37.94' Fence Post ACT 132 FORMS L 2, P 641, Swartz Same as L 2, Page 535, R M-7 to M-6, 2647.79', L 5, P 865-866 Elrich, 4-30-80, same as L 2, Page 535, L 5, P 481 Elrich, 9-4-79 same as Swartz, Kay L 001, Page 901, 1-8-73, NW 1/4 Cor, 19-10-12, N 70° W 33.45' Nail Gate Post, N 20° W 153.8' 16" Maple, East 30.25' Nail Cor Post. M-7 to M-8 2649.85 UNRECORDED INFORMATION Survey Kennedy 7-10-78, Job # 78-1138, M-8 to M-7 2642.59 same witnesses as Liber 3, Page 48

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Gravel Road, Jog in Brush line Found 1/2" Iron in C/L Road, Occupation to West, Found 1/2" Iron 6.68' North, Occupation to East. Found Stake, 33' West, M-7 to M-8 2642.14' M-7 to M-6 2654.50' M-7 to A-7 6.68'

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

Ray Davis
RAY DAVIS P.S. CO. SURVEYOR
DATE 12-14-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

November 7, 1994
Found 1/2" Iron in C/L Road, Set Brass Cap
N 6.68' 1/2" Rerod
S 73° 53' W 36.03' NAIL AND TAG N/S 6" ELM
N 55° 30' W 41.44' NAIL AND TAG N/S 6" SQ WD POST
N 27° 53' W 38.42' TOP N END 12" CMP
S 85° E 39.58' W FACE STEEL SIGN
Note Corner accepted by LCRC is not the corner used by Swartz and HBE, they reference A-7, T10N-R12E



Signed by *Earl E. Gravlin* Date 12/13/94

Surveyor's Michigan License No. 23510