

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Lapeer</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 10N R 11E	M-8
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD

94 DEC 14 AM 10:45

LIBER NO. 005 PAGE NO. 157

REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Earl E. Gravlin, in a field survey on September, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Parke 1833, P 488, Set Stake, Birch 16 N10.5W 9.5, Hemlock 10 S 14 W 40. L 3, P 48, 1-4-79, Kennedy, EAST 31.64' 22" Aspen, S 80° W 20.71' 6" Apple, Elrich, L 3, P 550, 12-5-79 N 80° E 31.65' 28" Maple, N 40° W 61.5' 24" Ash, WEST 32.95' 1/2" Iron, S 75° W 20.75' 8" Apple, L 1, P 183, 11-29-74, Swartz, A-8, 10-12, 1/2" Rebar, N 85° E 31.4' Nail in 20" Maple, WEST 27.5' Nail in fence post, N 30° W 61.6' Nail in Boxelder L 005, P 859 Elrich, Same Witnesses 19-10-12, L 005, P 481 Elrich, same witnesses 19-10-12, L 010, P 330, Elrich, 4-26-93, N 80° E 31.65' 25" Apple, S 75° W 20.75' 8" Apple, WEST 31.50' Power Pole, EAST 32.90' 3/8" Iron, N 40° E 31.90' 5" Apple, Reset From Ties, Kay L 1, P 901, 1-8-73, W 1/4, Cor, 19-10-12, West 27.8' Nail in Cor Post, N 45° W 81.95' 12" Box Elder, N 85° e 31.6' 20" Maple, M-8 to M-7, 2649.85'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Gravel Road, Good occupation, Fence West, Brush Row to East, Found 1/2" Iron in Road. Common to Burnside corner A-8, M-8 to M-9 2650.10' M-8 to M-7 2642.14'.

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

RAY DAVIS P.S. CO. SURVEYOR
DATE 12-14-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

November 7, 1994
Found 1/2" Iron. Set brass cap
S 75° W 20.68' N/S NAIL AND TAG 8" APPLE
WEST 31.52' S/S NAIL AND TAG POWER POLE
N 80° E 31.65' N/S NAIL AND TAG 24" MAPLE
N 15° E 99.82' W/S NAIL AND TAG 8" ASH



Signed by [Signature] Date 12/15/94
Surveyor's Michigan License No. 23510

LIBER 0005 PAGE 0157