

SURVEY & REMONUMENTATION

APR 28 1995

REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Lapeer County Located In: Corner Code #44

1. Public Land Survey	T <u>10N</u> R <u>11E</u>	<u>M-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECEIVED FOR RECORD

94 DEC 14 AM 10:46

LIBER NO. 005 PAGE NO. 158

Robert DeLoach

REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Earl E. Graylin, in a field survey on September, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Parke 1833, P 487, Set Stake, Hemlock 10" 32.5, Hemlock 16" N 41 W 31.5, Wampler, 1834, Page 686 Common Corner W Oak 13 S 52 E 26, Pine, 36 N 23 E 41. ACT 74 FORMS L 3, P 584, Elrich A-9-10-12, SW 19-10-12, N 45 W 55.23' TP, S 60 W 71.6' CONC. MARKER, N 50 E 81.15' PP, L 1, P 898, Kay, 1-2-73, 30-10-12, N 40 W 55.3' NAIL TP, N 50 E 81.4' NAIL PP, S 60 E 75.05' NAIL 20" OAK, L 10, P 330 Elrich 4-26-93 S 60 W 71.5' CONC. MARKER, N 50 E 81.15' PP, S 55 E 75.30' 14" OAK, N 45 W 53.61' TP, FOUND 5/8" IRON. ACT 132 FORMS L 5, Page 859, Elrich, same as L 5, P 859

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Flat land, gravel road North-South, gravel road East-West. Found 1/2" Iron. M-9 to M-10 2573.27' M-9 to M-8 2640.12 M-9 to A-10 2606.27

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

Ray Davis
RAY DAVIS P.S. CO. SURVEYOR
DATE 12-14-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

November 7, 1994
Found 1" Bar in Mon. Box, Set 1/2" Iron and Brass Cap
N 46 30' E 81.08' NAIL AND TAG POWER POLE
N 41 14' W 53.52' NAIL AND TAG TELE. POLE
N 50 56' W 115.56' SE CORNER HOUSE
S 53 37' E 75.18' NAIL AND TAG 15" OAK



Signed by *Earl E. Graylin* Date 12/13/94
Surveyor's Michigan License No. 23510