

SURVEY &  
REMONUMENTATION

1993

COMMISSION

REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

93 DEC 22 PM 3:09

LIBER 5 38  
LAFAYETTE COUNTY CLERK

For corners in

LAPEER  
(County)

Located In:

Corner Code #

- |                                    |                           |             |
|------------------------------------|---------------------------|-------------|
| 1. Public Land Survey              | T <u>10N</u> R <u>11E</u> | <u>M-11</u> |
|                                    | T _____ R _____           | _____       |
|                                    | T _____ R _____           | _____       |
|                                    | T _____ R _____           | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____       |
|                                    | S _____ T _____ R _____   | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____       |
|                                    | S _____ T _____ R _____   | _____       |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Earl E. Gravlin, in a field survey on October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-11. Northeast corner Section 36 History: East and South town lines run by Hervey Parke, 1834. Pages 486 and 487. Subdivision of township run by Hiram Burnham, third quarter, 1834. page 496-498. Witnesses Beech 11 N 57°W .17 Do S3°W .12 set post. County Surveyors Record: Book 2, page 146, Stone East quarter corner. Recorded survey L 009 P 541

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Site conditions: Flat farmland Peck Road(Gravel) east & west.  
No fences to north or south. Found railroad spike in place in centerline of road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

October 20, 1993  
M-11  
Replaced railroad spike with 1/2" iron with brass cap  
N 87°E 762.44' NAIL & TAG 24" OAK  
S 74°E 197.56' NAIL & TAG POWER POLE  
S 73°W 219.40' NAIL & TAG POWER POLE  
N 69°W 392.14' SE. COR. BASEMENT, HSE #5965



Signed by [Signature] Date 12-02-93  
Surveyor's Michigan License No. 23510