

SURVEY &
REMONUMENTATION

1993

COMMISSION

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

93 DEC 22 PM 3:11

LIBER 5 40
LAPPEER

For corners in

LAPPEER
(County)

Located In:

Corner Code #

- | | | | | | |
|---------------------------------------|---|------------|---|------------|-------------|
| 1. Public Land Survey | T | <u>10N</u> | R | <u>11E</u> | <u>M-13</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |
| 4. Lot No. _____, Recorded Plat _____ | | | | | |
| 5. Private Claims _____ | | | | | |

Register of Deeds Stamp & File Number

I, Earl E. Gravlin, in a field survey on October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-13. Southeast corner Section 36
History: East and South town lines run by Hervey Parke, 1834. Pages 486 and 487
Subdivision of township run by Hiram Burnham, third quarter, 1834. page 496-498
Witnesses Elm 16 S16°W .13 B Ash 16 N5°W .16 Set post
County Surveyors Record: Book 2, page 146, Stone East quarter corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Site conditions: flat farmland abandoned road east & west ditch to south, fence to north
Found 1/2" iron lying on ditchbank, apparently disturbed by recent ditch cleaning. Re-set corner on extension of north south fences in center of old east west road bed.
MEASUREMENT M-13 TO M-12 2632.91

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

October 20, 1993
M-13
Re-set 1/2" iron with brass cap on extension of north south fences in center of old east west road bed.
N20°W 22.18' NAIL & TAG 6" ASH
S55°W 41.45' NAIL & TAG 12" ELM
S05°E 38.26' NAIL & TAG 20" ASH
N05°W 68.01' NAIL & TAG 12" ASH



Signed by [Signature] Date 12-02-93

Surveyor's Michigan License No. 23510