

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 NOV 18 PM 1:50

LIBER NO. 05 PAGE NO. 110

Richard D. Kraft
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

For corners in
Lapeer
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>10N</u> R <u>12E</u>	<u>L-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, Earl E. Gravlin, in a field survey on September, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

PARKE 1833, P 267, SET POST, HEMLOCK, 12, N 30W 15, SUGAR 17, N 84 E 45.5 ACT 132 FORMS L 4, P 433, KAY, 11-9-77, FOUND 1/2" IRON, N 20°W 28.15' NAIL 28" OAK, S 35°E 26.20' 8" BOX ELDER, EAST 20.0' N 1/4 COR. 1-9-12.

UNRECORDED INFORMATION Revision to Kay survey, 7-26-84, L-13 to M-13 2665.26'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Gravel Road. Found 1/2" Iron. L-13 to K-13, 2665.15' L-13 to M-13, 2665.07'

PEER GROUP
APPROVED LAND CORNER
PA 245 OF 1990
LAPEER COUNTY
Ray Davis
RAY DAVIS P.S. CO. SURVEYOR
DATE 11-18-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1/2" Iron, Set Brass Cap
S 53°28'W 36.61' NAIL AND TAG N/S 6" ASH
N 20°25'W 27.20' NAIL AND TAG E/S 28" OAK
N 25°31'E 16.15' NAIL AND TAG W/S 6" ASH
N 51°52'E 29.03' NAIL AND TAG S/S 6" ASH
EAST 20.03' NORTH 1/4 COR. 1-9-12, FOUND IRON



Signed by *Earl E. Gravlin* Date 11/18/94
Surveyor's Michigan License No. 23510

LIBER 0005 PAGE 0110