

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 NOV 18 PM 1:51

LIBER NO. 05 PAGE NO. 111

REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

For corners in <u>Lapeer</u> <small>(County)</small>	Located in:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>12E</u>	<u>M-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Earl E. Gravlin, in a field survey on September, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	0	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Wampler 1822, Set Post, Maple 8 N14W 48, Elm 11 S71W 62, Burt 1834 intersected 1.10 links North, corrected, Elm 4 S70 E 25, Elm 10 N67E 95. ACT 74 FORMS L 1, P 159, 1974 Swarts, found stone over 4" wood post, Set Iron, N 60° E 58.9' 16" Ash, N 70° W 41' 20" Ash, North, 23.1' Cor Post. ACT 132 FORMS L 3, P 18, Swarts, Same as L 1, P 159, L 3, P 460 HBE, Found 1/2" Iron, N 70° W 41.5' 20" Ash, N 01° E 23.8' Cor. Post, N 40° E 47.26' 8" Apple, N 65° E 59.55' 12" Ash, L 2, P 425, Swarts, same as L 1, P 159, L 3, P 19, same as L-1, P 159 M-7 - L-7 2621.52'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Gravel Road East and West, Gravel Road South, Fence remains North. Found 1/2" Iron M-7 to M-8 2644.02, M-7 to L-7, 2621.58'

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

RAY DAVIS P.S. CO. SURVEYOR
DATE 11-13-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

November 7, 1994
Found 1/2" Iron, Set Brass Cap
M N 70° W 124.66' NAIL AND TAG N/S 36" ASH
N 18° 19' W 48.19' NAIL AND TAG W/S 4" APPLE
S 14° 14' E 118.01' NAIL AND TAG W/S 12" WILLOW
WEST 2621.58' N 1/4 COR. 24-10-12
S 67° 27' W 93.47' NAIL AND TAG N/S 8" ASPEN



Signed by _____
Surveyor's Michigan License No. 23510

Date 11/13/94