

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 NOV 18 PM 1:59

LIBER NO. 05 PAGE NO. 119

Malcolm D. Laugh
REGISTER OF DEEDS
LAPPEER COUNTY MICHIGAN

For corners in
Lapeer (County) Located In: Corner Code #

1. Public Land Survey	T <u>10N</u> R <u>12E</u>	M-8
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Earl E. Gravlin, in a field survey on September, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Wampler, 1822, Set Post, Sugar 11 N86W 1 1/2, Hem, 40 N61W 23.

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPPEER COUNTY

Ray Davis
RAY DAVIS P.S. CO. SURVEYOR
DATE 11-13-94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Rolling Land, Gravel Road, Corner post with wind brace to West, Corner post, fence and brush row to East. Found 3/4" IRON 2'± W OF ROAD C/L. Common to Flynn Township Corner. M-8 to M-9 2640.12' M-8 to M-7 2644.02'

C. Description of monument for corner and accessories established to perpetuate locating the corner:

November 7, 1994
Found 3/4" IRON 2'± W OF ROAD C/L, Replaced with 1/2" Iron with Brass Cap
S 80°W 43.17' NAIL AND TAG N/S 8" CHERRY
S 75°E 35.10' NAIL AND TAG S/S 12" CHERRY
N 25°W 48.58' NAIL AND TAG E/S 6" ELM
S 15°E 71.05' NAIL AND TAG W/S 30" ASPEN



Signed by *Earl E. Gravlin*
Surveyor's Michigan License No. 22510

Date 11/17/94