

SURVEY & REMONUMENTATION

1993

COMMISSION

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

93 DEC 22 PM 3:01

LIBER 5 FILE NO. 30

For corners in

LAPEER (County)

Located In:

Corner Code ##

- 1. Public Land Survey T 10N R 12E M-11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

I, Earl E. Gravlin, in a field survey on October, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-11. Northeast corner Section 36. History: East town lines run by Joseph Wampler, 1821. Page 670 North west and south lines run by Hervey Parke 1833 page 667. Subdivision of township run by Hiram Burnham, 1834. page 667. Witnesses Hemlock 8 S6°W .24 Beech 9 N75.5°W 3.5 set post. County Surveyors Record: Nothing. Recorded surveys Nothing. Unrecorded surveys Kay 3/26/85 30-10-13

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Site conditions: Slightly rolling farmland. Intersection Peck Road(bit) and Cade Road(gravel) Found 1/2 " iron in place Good occupation appears to be common corner. MEASUREMENT M-11 TO M-12 2624.91 M-11 TO M-9 5212.54 M-11 TO A-10(10-13) 2606.27 M-10 TO M-9 2639.27

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

October 15, 1993 Found 1/2 " iron in place, set brass cap S40°E 71.15' NAIL & TAG N SIDE POWER POLE S40°E 41.10' 2" PIPE ROAD SIGN S40°W 62.70' FACE GTE JUNCTION BOX N30°W 51.10 FACE GTE JUNCTION BOX Lapeer County Road Commission Set Monument Box



Signed by

[Signature]

Date

12-2-93

Surveyor's Michigan License No.

23510