

SURVEY &
REMONUMENTATION

1993

COMMISSION

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

93 DEC 22 PM 3: 03

LIBER 5
PAGE 32
LAPPEER
MICHIGAN

For corners in

<u>LAPPEER</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>12E</u>	<u>M-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Earl E. Gravlin, in a field survey on October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-13. Southeast corner Section 36. History: East town lines run by Joseph Wampler, 1821. Page 670 North west and south lines run by Hervey Parke 1833 page 667. Subdivision of township run by Hiram Burnham, 1834. page 667. Witnesses Hemlock 16 S6° E .37 Do 11 N39° E .29 set post. County Surveyors Record: Nothing. Recorded surveys L004 P 175 Kay 1-9-12.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Site conditions: Flat farmland Intersection Stiles Road(gravel) and Cade Road(gravel)
Found 1/2 " iron in place
Good occupation
MEASUREMENT M-13 TO M-12 2624.50'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

October 15, 1993
Found 1/2 " iron in place, set brass cap
N55° W 38.06' NAIL & TAG N SIDE GTE POLE
N47° E 34.98' NAIL & TAG NW FACE FENCE POST
N82° E 86.25' NAIL & TAG S SIDE 6" ELM
S45° E 75.48' NAIL & TAG SW FACE POWER POLE



Signed by [Signature] Date 12-02-93
Surveyor's Michigan License No. 23510