

SURVEY & REMONUMENTATION

FEB 26 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Leelanau
(County)

Located In: _____ Corner Code # _____
T 28NR 12W M-6(Elmwood Twp)
 T _____ R _____
 T _____ R _____
 T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

Barbara Kirt 12/30/97
 Leelanau Res of Deeds 2:11 PM
 BJK Fee: 9.00
 04800002 P0200 Page 1 of 1

#505

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Steven P. Bye, in a field survey on December 10, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-6: East 1/4 corner of Section 13
 G.L.O. notes: set 1/4 post - Sugar 24 S32W 19 lks.
 Hemlock 15 S40E 37lks.
 1948 H. H. Brehmer field book 10 - i.p at corner
 1973 Glenn Delamater found 3/4" iron & filed L.C.R.C. #64

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6: East 1/4 corner of Section 13
 3/4" i.p. found on side slope at westerly side of Mann Road.
 Delamater witnesses
 18" ash N80°W 71.49'
 Tele. pole S55°W 105.50'
 Guy pole N45°E 142.88'
 12" walnut S45°E 79.80'

APPROVED LAND CORNER
 P.A. 345 OF 1990
 LEELANAU COUNTY
 DATE: 11-17-97
 COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6: East 1/4 corner of Section 13
 3/4" iron pipe accepted as the best available evidence of the position of the original corner by the Leelanau County Remonumentation Peer Review Group on November 17, 1997 and replaced with a 3/4" galvanized iron pipe 3' long with a brass cap.
 Witnesses: 18" ash N80°W 71.49' Tele. pole S55°W 105.50'
 Guy pole N45°E 142.88' 12" walnut S45°E 79.80'

Signed by [Signature]
 Surveyor's Michigan License No. 35991

Date 12-12-97

