

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES  
LAND CORNER RECORD

EEELANAU COUNTY


T 28 N R 13 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 25 & 26

CORNER MONUMENT Set Std. Dept. Mon (buried) in approx. Center of N-S  
Gravel Road

DATE MONUMENT PLACED AND WITNESSED 7-1-69

WITNESSES TO CORNER..... 9" Ash S 23 E 119.0'



20" Beech N 80 W 73.3'

Set Cor. Post Due E 33'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set during a retracement of boundary survey in this area. The corner was set by single proportion (to U.S.) between found section corner to the South and established section corner to the North. The corner is in line with old field edge to E & W.

SURVEYOR'S SEAL

SIGNED

*Carl F. Roer*  
REGISTERED LAND SURVEYOR 12028

DATE

8-8-69

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68