

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

LEKLAUNAU COUNTY


T 28 N R 13 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 25 & 36

CORNER MONUMENT Set 1"x20" pipe in black top road (M-72)

DATE MONUMENT PLACED AND WITNESSED 7-1-69

WITNESSES TO CORNER..... 22" Maple S 34 W 129.5'



12" B. Cherry Tree S 3 W 98.5'

Set PK Nail (Trv. Point) N89°12'W 1.52'

AND

Set Cedar Post Due N 33'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set during a retracement and boundary survey in this area. It was set by single proportion (to U.S.) between found section corners to E & W.

SURVEYOR'S SEAL

SIGNED

Carl F. Roer

DATE

8-8-69

DISTRIBUTION:

REGISTERED LAND SURVEYOR 12028

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68