

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES  
LAND CORNER RECORD

LEKLANAU COUNTY


T 28 N R 13 W

DESCRIPTION OF CORNER Sec. corner common to Sections 23-24 25-26

CORNER MONUMENT Set Std. Dept. Men buried in gravel road intersection N-S-E-W.

DATE MONUMENT PLACED AND WITNESSED 4-30-69

WITNESSES TO CORNER..... Side Nail P. Pole with Transf. S 24 W 177.27'



Side Nail P. Pole N 25 W 154.78'

Side Nail P. Pole N 81 E 159.50'

AND

Cor. Pa. Post N 54 E 48.7'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set during a retracement and boundary survey in this area. The corner was established by average lines of occupancy (fences and roads) for one mile to the E, W, & S, and for one-half mile to the N. An approximate corner 1/2" reinforcing rod set by the County Road Commission has been removed. The 1/2" rod was N 1°03'W, 4.53' from the Std. Dept. Men.

SURVEYOR'S SEAL

SIGNED

*Carl F. Roever*

DATE

8-8-69

DISTRIBUTION:

REGISTERED LAND SURVEYOR 12028

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68