

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES  
LAND CORNER RECORD


LEHMAN COUNTY  
T 28 N R 12 & 13 W

DESCRIPTION OF CORNER Sec. corner common to Sections 24-19 25-30

CORNER MONUMENT Set Std. Dept. Men with Cedar guard post

DATE MONUMENT PLACED AND WITNESSED 7-1-69

WITNESSES TO CORNER..... 12" Ash N 32 E 9.1'



7" Maple N 76 W 25.9'

E-W Gravel Road Due N 45' ±

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set during a retracement and boundary survey in this area. The corner falls in the remains of an old N-S fence at the edge of an old woods and field line. The corner as established fits very close to single proportion (to U.S.) between found section corners to the N & S one mile.

SURVEYOR'S SEAL

SIGNED

*Carl F. Roser*

DATE

8-8-69

DISTRIBUTION:

REGISTERED LAND SURVEYOR **12028**

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68