

Lansing - Forestry
LEELANAU COUNTY

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Raw copy

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>28</u> N. R. <u>13</u> W.	G-13; H-13; I-12
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on 4-11 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-13 Recovered corner - fits old line fence remains N and road alignment for 3/4 of mile to N.
- H-13 Restored corner on line and at prop. distance to U.S., between the SE S-34(I-13) and the SW S-34(G-13)
- I-12 Reestablished corner in center of N-S dirt County Road and in line with old line fence to West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12	G-13	H-13
Set DNR Monument	Fd. 1 1/2" well pt. Added DNR	Set DNR Mon. & Cedar Gd.
P. Pole N20E 111.70	Mont. & Cedar Gd. Post	Post
Steen cor fn post	12" Maple N88W 47.9'	7" Maple S61E 45.5'
S81E 35.0'	12" Maple N54E 34.5'	14" Maple N45W 7.4'
Set Ced. Post	14" Maple N40W 2.5'	24" Hemlock N 9E 37.7'
w/loc tag Due W 33'	14" Ironwood S12W 18.0'	
	E-W B.wire fn Due N 2.5'	


SIGNED BY Carl F. Roser DATE 7-16-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____