

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
LEELANAU
 (County)

Located In: _____ Corner Code M-11

- | | | | | | | |
|------------------------------------|---|------------|---|------------|-------------|-------|
| 1. Public Land Survey | T | <u>29N</u> | R | <u>12W</u> | <u>M-11</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, C.F. ROSER, in a field survey on 9-10, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
M-11

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-11

FD CON MON, WITH BRASS CAP
 BONE, AS SET IN 1942 SURVEY BY
 LS's H.H. BREHMER & G. SHADKO.
 *MON SET IN PLACE OF FOUND 1"
 IRON PIPE AND A FORD AXLE
 SHAFT WITH GEAR ON TOP (ALSO
 OLD BRICKS AND FRAGMENTS OF
 CAST IRON PIPE)*, PER H.H.
 BREHMER - G. SHADKO, DEC. 1942.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-11

FD CON MON, RAISED W/1" x 6"
 GALV. PIPE W/LS CAP.
 12" TW. CEDAR N35°E 45.20'
 SE COR WOOD FRAME
 BLDG. N25°W 45.0'
 CON MON W/BRASS
 CAP SOUTH 33.00'
 DROVE 5/8" x 17" ROD
 W/LS CAP WEST 106.28'
 CON MON EAST 329.87'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by Carl F. Roser 12028 12-20-91 Date

Surveyor's Michigan License No. _____

