

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF LEELANAU  
RECEIVED FOR RECORD

1993 DEC 28 PM 4: 26

*Barbara Kirt*  
REGISTER OF DEEDS

FILE #340

LIBER 2 PAGE 37

Register of Deeds Stamp & File Number

For corners in  
Leelanau  
(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 29N R 12W      G-1  
    T \_\_\_\_\_ R \_\_\_\_\_  
    T \_\_\_\_\_ R \_\_\_\_\_  
    T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling      S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    in Section                    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    Property in Sec.            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Steven P. Bye, in a field survey on December 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G-1: NE corner Section 4:      G.L.O. "Set post corner to sections 3 & 4"  
    Beech 10, S 28 W, 12 links  
    Beech 10, S 80 E, 21 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1: NE corner Section 4:      1/2" x 24" iron rod found 1.5' below surface on North edge of driveway. This is also S 10 W, 1.09' from found 5/8" iron rod and cap #19846 (Weinert). Both Batzer Jr. and Weinert filed Land Corner Certificate.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1: NE corner Section 4:      The Leelanau County Remonumentation Peer Review Group voted November 29, 1993 to accept the Batzer Jr. iron (file #75) and reject the Weinert corner (file #199). The Batzer Jr. iron was replaced with a 3/4" i.d. galvanized iron pipe 3' long with a brass cap.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by

*Steven P. Bye*

Date

12-20-93

Surveyor's Michigan License No.

35991

