

1993

COMMISSION

STATE OF MICHIGAN
COUNTY OF LEELANAU
RECEIVED FOR RECORD

1993 DEC 28 PM 4: 26

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Leelanau
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 29N R 12W H-1
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Barbara Kirt
REGISTER OF DEEDS

FILE #342

LIBER 2 PAGE 39

Register of Deeds Stamp & File Number

I, Steven P. Bye, in a field survey on December 9, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-1: N 1/4 corner Section 3: None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-1: N 1/4 corner Section 3: Granite stone found with "X", and iron rod with cap #28420 South 0.40', 23' South of centerline of Lavassar Road. This corner was set by C.P. Tuller in 1893 from original witnesses and is filed by Theodore H. Weinert (file #200).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H 1: N 1/4 corner Section 3: Granite stone accepted by the Leelanau County Remonumentation Peer Group, November 29, 1993, and replaced with a 3/4" i.d. galvanized iron pipe 3' long with a brass cap. The iron bar and cap #28420 was removed to avoid confusion.

- Maple cluster - West 7.85' (record)
- 5/8" iron rod and cap #19846 - East 83.16' (S 1/4 Sec. 34 T30N R12W)
- 8" ash - S 80 E, 88.23'
- 8" maple - S 43 E, 101.44'
- 5" spruce - S 02 E, 36.77'

Signed by Steven P. Bye Date 12-20-93

Surveyor's Michigan License No. 35991

