

**SURVEY &
REMONUMENTATION**

FEB 26 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Leelanau</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T29N R12W	H-3
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Barbara Kirt 12/31/97
Leelanau Res of Deeds 10:25 am
BJK Feet 9.00
04B00002 F0242 Page 1 of 1

#545

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Nicholas M. O'Non, in a field survey on Dec. 4, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3								●				
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-3: 1/4 Corner Common To Sections 3 and 10.
G. L.O. Notes: 1/4 Post, Nov. 29, 1851
Beech 8", N30°W, 48 Links
Sugar 12", South, 9 Links

Fred Greene: Stone w/x on top, April 1911.
Beech 14", North, 19½ Links

Stone Corner found by numerous surveyors since.

**APPROVED LAND CORNER
P.A. 345 OF 1990
LEELANAU COUNTY**

DATE: 11-24-97
COUNTY REP. N.M.O'Non

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

II-3: 1/4 Corner Common To Section 3 and 10
Found 1.5' x 0.8' x 0.7' Granite Stone w/x on top.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-3: 1/4 Corner Common To Sections 3 and 10
Granite Stone w/x accepted as a careful and faithful perpetuation of the position of the original corner by the Leelanau County Peer Review Group on November 24, 1997. Replaced with a 3/4" I.D. by 3.0' long galvanized iron pipe with a stamped brass cap.
8" Maple, N58°E, 6.48'
12" Maple, S33°E, 10.09'
5" Ash, S53°W, 9.10'
4" Ash, N20°W, 6.75'

Signed by Nicholas M. O'Non
Surveyor's Michigan License No. 28420

Date 12-30-97

