

**SURVEY & MONUMENTATION**

MAR 15 2000

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Barbara Kirt  
Leelanau Reg of Deeds  
BJK Fee: 9.00  
04B00002 P0360  
12/30/99  
3:34 PM  
Page 1 of 1

For corners in

Leelanau  
(County)

Located In:	Corner Code #
T <u>30N</u> R <u>11W</u>	<u>A-7</u>
T ___ R ___	_____
T ___ R ___	_____
T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Nicholas M. O'Non, in a field survey on Dec. 9, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-7: West Section Corner common to Sections 18 and 19  
G.L.O. Notes: Set post corner to Sections 18, 19, 13 and 14  
Beech 4", N 21° W, 21 Links  
Sugar 6", S 14° W, 19 Links  
Hemlock 16", S 49° E, 21 Links  
Beech 20", N 06° E, 34 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7: West Section Corner common to Sections 18 and 19  
Found 1/2" iron rod w/cap No. 28420 per N.M. O'Non Certificate of Survey File No. 8857-19SB3011, September 16, 1988.  
36" Maple, West, 365.51'  
12" Sweet Cherry, S 10° E, 26.80'  
7" Sweet Cherry, S 62° W, 48.66'

APPROVED LAND CORNER  
P.A. 345 OF 1990  
LEELANAU COUNTY  
DATE: 12-8-99  
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7: West Section Corner common to Sections 18 and 19.  
1/2" iron rod w/cap no. 28420 accepted as a careful and faithful reestablishment of the position of the original corner by the Leelanau County Peer Review Group on December 8, 1999, and replaced with a 3/4" dia. by 36" long galvanized iron pipe with a stamped brass cap.  
36" Maple, West, 365.51'  
12" Sweet Cherry, S 10° E, 26.80'  
7" Sweet Cherry, S 62° W, 48.66'  
Phone Pole, N 10° E, 120.56'

Signed by [Signature]  
Surveyor's Michigan License No. 28420

Date December 29, 1999

