

1994 DEC 30 AM 10:39

**SURVEY &
REMONUMENTATION**

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Leelanau
(County)

APR 10 1995

Located In:

Corner Code ##

Barbara Kirt
REGISTER OF DEEDS

#384

LIBER 2 PAGE 81

Register of Deeds Stamp & File Number

- 1. Public Land Survey 30N R 11W B-1
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling _____
in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		13		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Nicholas M. O'Non, in a field survey on December 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-1: North 1/4 Corner of Section 6
G.L.O. Notes: Set 1/4 Sec. post per A. S. Wadsworth Survey Oct. 22, 1851.
Hemlock 24", S 51° W, 14 Links
Hemlock 38", S 75° E, 47 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1: North 1/4 Corner of Section 6
Set 1/2" x 24" rerod with cap no. 28420 on fence line South and on line between Standard Corners for T31N, R11W, per N.M. O'Non Cert. of Survey File No. 9123-311L3111-R., rev. Feb. 12, 1992.
14" Yellow Birch, N 35° E, 32.53'
7" Cedar, S 05° W, 23.68'
12" Maple, N 35° W, 51.20'

APPROVED LAND CORNER
P.A. 345 OF 1990
LEE LANAU COUNTY
DATE: 10-5-94
COUNTY REP. N.M. O'Non

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1: North 1/4 Corner of Section 6
Found 1/2" x 24" rerod with cap no. 28420
Accepted by Leelanau County Remonumentation Peer Review Group Oct. 5, 1994. Replaced with 3/4" I.D. galvanized iron pipe 3.0' long with stamped brass cap.
9" Ash, S 45° W, 25.91
14" Yellow Birch, N 35° E, 32.53'
7" Cedar, S 05° W, 23.68'
12" Maple, N 35° W, 51.20'



Signed by Nicholas M. O'Non Date DECEMBER 28, 1994
Surveyor's Michigan License No. 28420

#384