

**SURVEY &
REMONUMENTATION**

1993

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF LEELANAU
RECEIVED FOR RECORD

1993 DEC 28 PM 4: 27

Barbara Kirt
REGISTER OF DEEDS

FILE #344

LIBER 2 PAGE 41

Register of Deeds Stamp & File Number

For corners in

Leelanau

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>30N</u> R <u>11W</u>	<u>C-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Steven P. Bye, in a field survey on December 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-1: NE corner, Section 6: G.L.O. "Set post corner Sections 5 & 6 in swamp"
Cedar 10 - S 77 W, 14 links
Cedar 14 - S 86 E, 22 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-1: NE corner, Section 6: Found 1" i.d. iron pipe on old E-W fenceline, fitting witnesses of record. Top of pipe smeared with green paint.

Existing witnesses:

12" cedar in fenceline West, 29.33'
8" Hemlock - N 20 W, 9.69'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1: NE corner Section 6: 1" i.d. iron pipe accepted by the Leelanau County Remonumentation Peer Group, December 9, 1993, and replaced with a 3/4" i.d. galvanized iron pipe 3' long with a brass cap.

12" Cedar in fenceline - West 29.35'
8" Hemlock - N 20 W, 9.69'
13" Cedar - S 85 E, 20.42"
4" Ash - S 25 E, 10.48'

Signed by *Steven P. Bye*

Date 12-21-93

Surveyor's Michigan License No. 35991

