

**SURVEY &  
REMONUMENTATION**

**MAR 15 2000**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Leelanau</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>30N</u> R <u>11W</u>	<u>C-7</u>
	T <u>    </u> R <u>    </u>	_____
	T <u>    </u> R <u>    </u>	_____
	T <u>    </u> R <u>    </u>	_____
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	_____
	S <u>    </u> T <u>    </u> R <u>    </u>	_____
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	_____
	S <u>    </u> T <u>    </u> R <u>    </u>	_____

Barbara Kirt 12/30/99  
Leelanau Res of Deeds 3:30 pm  
BJK Fee: 9.00  
04800002 P0358 Page 1 of 1

#661

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Nicholas M. O'Non, in a field survey on Dec. 11, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7			●										
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-7: Section Corner common to Sections 17, 18, 19 and 20  
G.L.O. Notes: Section Cor. 17, 18, 19 and 20  
Beech 10", N42°W, 8 Links  
Hemlock 20", S22°E, 9 Links

T.H. Weinert, 1977: Found Old Axle

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-7: Section Corner common to Sections 17, 18, 19 and 20  
Found axle shaft with 8" dia. hub  
Power Pole, S89°E, 68.82'  
Power Pole, S72°W, 65.33'  
NE Corner on E'ly Ell of House, S50°W, 142.65'

**APPROVED LAND CORNER  
P.A. 345 OF 1990  
LEELANAU COUNTY**

DATE: 12-8-99

COUNTY REP. N. M. O'Non

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7: Section Corner common to Sections 17, 18, 19 and 20  
Axle Shaft with hub accepted as the best available evidence of the position of the original corner by the Leelanau County Peer Review Group on December 8, 1999, and replaced by a 3/4" dia. by 36" long galvanized iron pipe with a stamped brass cap.  
NE Cor. on E'ly Ell of house, S53°W, 142.74'  
Power Pole, S70°W, 67.34'  
NE Cor. of Barn, South, 132.92'  
W'ly 4"x4" Sign Post, S66°E, 115.32'

Signed by Nicholas M. O'Non  
Surveyor's Michigan License No. 28420

Date December 30, 1999

