

SURVEY & REMONUMENTATION

MAR 04 1999

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

Leelanau	Located In:	Corner Code #	
(County)			
1. Public Land Survey	<u>T 30N R11W</u>	<u>C-9</u>	
	T ___ R ___	_____	
	T ___ R ___	_____	
	T ___ R ___	_____	
2. Property Controlling in Section	S ___ T ___ R ___	_____	
	S ___ T ___ R ___	_____	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	
	S ___ T ___ R ___	_____	

Barbara Kirt 12/31/98
Leelanau Reg of Deeds 9:55 am
BJK Fee: 9.00
04800002 P0293 Page 1 of 1

#596

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Nicholas M. O'Non, in a field survey on December 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9			●										
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
C-9: Section Corner Common to Sections 19, 20, 29 and 30.
G.L.O. notes: Set post corner common to Sections 19, 20, 29 & 30, June 6, 1851

Beech 18", N38°W, 5 links
Beech 8", S66°E, 20 links

Iron Bar set by H. H. Brehmer, 1948
Witnesses:
6" Maple, N31°40'E, 24.1'
4" Elm, S18°20'E, 18.0'
4" Maple, S85°W, 24.1'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
C-9: Section Corner Common to Sections 19, 20, 29 and 30.
Found 5/8" iron rod.

Witnesses:
12" Maple, N04°W, 38.90'
8" Ash, S28°E, 28.90'
6" & 8" Dbl. Maple, N35°E, 49.58'
Under East-West power line

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
C-9: Section Corner Common to Sections 19, 20, 29 & 30.
5/8" iron rod accepted as the best available evidence of the position of the original corner by the Leelanau County Remonumentation Peer Review Group on December 10, 1998 and replaced with a 3/4" galvanized iron pipe 3' long and a stamped brass cap.

Witnesses:
Power Pole, N83°W, 40.23' 12" Maple, N04°W, 38.41'
4" & 10" Dbl. Maple, N35°E, 49.57' 10" Ash, S06°E, 30.16'
8" Ash, S28°E, 28.77' Under East-West Power line

**APPROVED LAND CORNER
P.A. 345 OF 1990
LEELANAU COUNTY**
DATE: 12-10-98
COUNTY REP. N.M. O'Non

Signed by Nicholas M. O'Non
Surveyor's Michigan License No. 28420

Date 12/29/98

