

SURVEY & REMONUMENTATION

FEB 26 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Leelanau</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>30</u> N R <u>11</u> W	C-11
	T <u> </u> R <u> </u>	_____
	T <u> </u> R <u> </u>	_____
	T <u> </u> R <u> </u>	_____
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____

Barbara Kirt 12/31/97
 Leelanau Res of Deeds 10:22 am
 BJK Fee: 9.00
 04B00002 P0234 Page 1 of 1

#537
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Nicholas M. O'Non, in a field survey on Dec. 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 C-11: Section Corner Common To Sections 29, 30, 31 and 32.
 G.L.O. Notes: Set Post Corner Sections 29, 30, 31 and 32, June 2, 1851.
 Beech 4", N45°W, 18 Links
 Beech 8", S34°E, 19 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 C-11: Sections Corner Common To Sections 29, 30, 31 and 32.
 Found 1/2" Rerod w/cap no. 28420
 18" Maple, North, 2.73'
 14" Maple, N30°W, 16.20'
 22" Maple, N73°E, 5.17'
 5" Maple, S55°E, 49.92'
 5/8" Rerod w/cap no. 19846, S0°28'W, 4.63'
 On East-West Fenceline.

APPROVED LAND CORNER
P.A. 345 OF 1990
LEELANAU COUNTY
 DATE: 12-1-97
 COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 C-11: Section Corner Common To Sections 29, 30, 31 and 32.
 1/2" Rerod w/cap no. 28420 accepted as the best available evidence of the position of the original corner by the Leelanau County Peer Review Group on December 1, 1997.
 Replaced with a 3/4" I.D. by 3.0' long galvanized iron pipe with stamped brass cap.
 18" Maple, North, 2.73' 5" Maple, S55°E, 49.92'
 14" Maple, N30°W, 16.20' 5/8" Rerod w/cap no. 19846,
 22" Maple, N73°E, 5.17' S0°28'w, 4.63'
 On East-West Fenceline.

Signed by [Signature]
 Surveyor's Michigan License No. 28420

Date 12-30-97

