

MAY 16 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Leelanau (County) Located in: Corner Code #
1. Public Land Survey T30NR11W D-11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Barbara Kirt 01/10/97
Leelanau Res of Deeds 11:23 am
BJK Fee: 9.00
04800002 P0179 Page 1 of 1

#482

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Nicholas M. O'Non, in a field survey on Oct. 31, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column D and row 11.

A. Description of original monument and accessories and/or subsequent restoration:

- D-11: 1/4 Corner Common to Sections 29 and 32. Iron Pipe Set From Old Witness Stumps Per H.H. Brehmer Survey in 1948.
4" Maple, S 47°30' W, 27.20'
10" Maple, S 60°30' E, 41.80'
10" Beech Stump, Southt, 9.6' (old wit)
15" Beech Stump, S 60± E, 14.2' (old wit)
20" Maple, N 21°30' E, 71.25'

P.J. O'Non Survey July 27, 1967
Found 1" Iron Bar.

- 6" Maple, North, 6.84'
12" Maple, S 70° E, 42.92'
12" Maple, S 60°30' E, 41.92' (old wit)
6" Maple, S 47°30' W, 27.20' (old wit)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-11: 1/4 Corner Common to Sections 29 and 32. Found 3/4" Iron Rod
10" Maple, N 10° W, 6.83' (old wit)
12" Maple, S 58° E, 41.96' (old wit)
14" Maple, S 14° E, 35.22'

APPROVED LAND CORNER
P.A. 345 OF 1990
LEELANAU COUNTY

DATE: 10-30-96
COUNTY REP. N.M. O'Non

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-11: 1/4 Corner Common to Sections 29 and 32. 3/4" Iron Rod accepted as a careful and faithful perpetuation of the location of the original corner by the Leelanau Peer Review Group on October 30, 1996. Replaced with 3/4" by 3.0' long galvanized iron pipe with stamped brass cap.
12" Maple, S58° E, 41.96' (old wit)
14" Maple, S 14° E, 35.22'
14" Maple, S 78° W, 39.86'
10" Maple, N 10° W, 6.83' (old wit)

Signed by Nicholas M. O'Non
Surveyor's Michigan License No. 28420

Date 12-30-96