

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF LEELANAU
RECEIVED FOR RECORD

1993 DEC 28 PM 4: 24

Barbara Kirt
REGISTER OF DEEDS

FILE #322

LIBER 2 PAGE 19

Register of Deeds Stamp & File Number

For corners in
Leelanau
(County)

Located In: Corner Code #

- 1. Public Land Survey T 30N R 11W E-1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

I, Steven P. Bye, in a field survey on December 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. A dot is marked in the cell at row 2, column E.

A. Description of original monument and accessories and/or subsequent restoration:

E-1: NE corner, Section 5: G.L.O. "Set post corner, section 4 & 5"
White ash - S 50 W, 4 links
Sugar - S 47 E, 30 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1: NE corner, Section 5: Found 3/4" i.d. 1-1/4" o.d. iron pipe on E-W & S fencelines
No other witnesses available

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1: NE corner, SECTION 5: 3/4" i.d. 1-1/4" o.d. iron pipe accepted by the Leelanau County Remonumentation Peer Group, december 9, 1993, and replaced with a 3/4" i.d. galvanized iron pipe 3' long with a brass cap set 2"-3" below surface of track.

New witnesses:
8" Wild apple - N 38 E, 19.77'
16" Scotch pine - S 78 E, 62.00'
8" Spruce - S 42 W, 112.25'
4" Wild apple - N 45 W, 112.41' (East most of clump)

Signed by Steven P. Bye Date 12-22-93
Surveyor's Michigan License No. 35991

