

**SURVEY &  
REMONUMENTATION**

MAR 15 2000

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Leelanau Located In: Corner Code #  
(County)

1. Public Land Survey T 30NR 11W E-7  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_

2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_  
in Section S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_  
Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_

Barbara Kirt 12/30/99  
Leelanau Reg of Deeds 3:29 PM  
EJK Feet 9.00  
04B00002 P0355 Page 1 of 1

#658

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Nicholas M. O'Non, in a field survey on Dec. 10, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-7: Section Corner common to Sections 16, 17, 20 and 21  
G.L.O. Notes: Set Post corner Secs. 16, 17, 20 and 21 (Wadsworth, 1851)  
Beech 12", N81°W, 45 Links  
Sugar 12", S49°E, 26 Links

T.H. Weinert, 1977: Set 5/8" iron bar with cap No. 19846

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-7: Section Corner common to Sections 16, 17, 20 and 21.  
Found 5/8" iron rod w/cap no. 19846  
10" Maple, S85°E, 29.34'  
11" Maple, S40°W, 37.23'  
15" Maple, N43°W, 16.98'  
6 ft. South of fenceline east  
6 ft. East of N-S fenceline

APPROVED LAND CORNER  
P.A. 345 OF 1990  
LEELANAU COUNTY

DATE: 12-8-99  
COUNTY REP. N. M. O'Non

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7: Section Corner common to Sections 16, 17, 20 and 21  
5/8" iron rod w/cap no. 19846 accepted as the best available evidence of the position of the original corner by the Leelanau County Peer Review Group on December 8, 1999.  
Replaced by a 3/4" dia. by 36" long galvanized iron pipe with a stamped brass cap.  
10" Maple, S85°E, 29.34' 18" Basswood, S02°E, 35.65'  
11 Maple, S40°W, 37.23' 6 ft. South of fenceline East  
15" Maple, N43°W, 16.98' 6 ft. East of N-S fenceline

Signed by Nicholas M. O'Non  
Surveyor's Michigan License No. 28420

Date December 30, 1999