

**SURVEY &
REMONUMENTATION**

MAR 04 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Leelanau (County)	Located In:	Corner Code #
1. Public Land Survey	T 30N R11W	E-9
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Barbara Kirt 12/31/98
Leelanau Rec of Deeds 9:54 am
BJK Fee: 9.00
04B00002 P0288 Page 1 of 1
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Nicholas M. O'Non, in a field survey on December 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

#591

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
E-9: Section Corner Common to Sections 20, 21, 28 and 29.
G.L.O. notes: Set post corner Sections 20, 21, 28 and 29, June 6, 1851

Beech 8", N4°W, 10 links
Elm 16", S69°E, 15 links

H. H. Brehmer replaced stone with concrete monument after 1945.
Witnesses:
8" Black Walnut, N72°45'W, 35.0'
10" Maple, S29°00'W, 15.1'
18" Elm, S0°30'E, 34.6'
14.5' East of fence corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
E-9: Section Corner Common to Sections 20, 21, 28 and 29.
Found 4" x 4" square concrete monument.

Witnesses:
27" Maple, S33°W, 15.48'
8" Maple in clump, N50°E, 29.41'
10" Basswood, N55°W, 27.62'
14.5' East of fence line south
On fence line west

**APPROVED LAND CORNER
P. A. 345 OF 1990
LEELANAU COUNTY
DATE: 12-10-98
COUNTY REP. *N. M. O'Non***

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
E-9: Section Corner Common to Sections 20, 21, 28 and 29.
4" x 4" square concrete monument accepted a careful and faithful perpetuation of the position of the original corner by the Leelanau County Remonumentation Peer Review Group on December 10, 1998. Monument was considered to be a superior marker and was left in place.

Witnesses:
27" Maple, S33°W, 15.49' Northwest corner of house, S30°E, 43.41'
8" Maple in clump, N50°E, 29.41' 14.5' East of fence line South
10" Basswood, N55°W, 27.60' On fence line West
Utility pole stump, S88°W, 23.11' 1/2" iron rod, West, 12.00'

Signed by *N. M. O'Non*
Surveyor's Michigan License No. 28420

Date 12/29/98

