

1995 DEC 29 PM 2:09

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Leelanau (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>30</u> N R <u>11</u> W	H-1
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

*Barbara Kirt*  
 REGISTER OF DEEDS

#429

LIBER 2 PAGE 126

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Nicholas M. O'Non, in a field survey on Nov. 15, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-1: North 1/4 Corner of Section 3.  
 H.H. Brehmer Survey in 1936 (Field Book IV, Page 37). Set iron pipe at North 1/4 Corner of Section 3.  
 22" Elm, N 33°30' E, 85.50'

APPROVED LAND CORNER  
 P.A. 345 OF 1990  
 LEELANAU COUNTY

DATE: 10-4-95

COUNTY REP. N. M. O'Non

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-1: North 1/4 Corner of Section 3.  
 Reset corner according to County Surveyor's Records, Book 3, Page 61, on Township Line 80.20' West of Standard Corner at the South 1/4 Corner of Section 34, Town 31 North, Range 11 West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-1: North 1/4 Corner of Section 3.  
 Corner location accepted as a careful and faithful reestablishment of the position of the original monument by the Leelanau County Peer Review Group on October 4, 1995. Set 3/4" by 3.0' long galvanized iron pipe with stamped brass cap in pavement box.  
 Power Pole, N 15° W, 33.38'  
 14" Ash, S 80° E, 140.06'  
 Power Pole, S 25° W, 44.27'  
 5" Pine, S 45° W, 220.56'  
 Stamped Brass Cap at S $\frac{1}{4}$  Cor. Sec. 34,  
 T31N, R11W, East, 80.20'

Signed by Nicholas M. O'Non

Date 12-29-95

Surveyor's Michigan License No. 28420

