

MAY 16 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Leelanau</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T30N R11W	I-10
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Barbara Kirt 01/10/97
 Leelanau Res of Deeds 11:32 am
 BJK Fee: 9.00
 04B00002 P0184 Page 1 of 1

#487

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Nicholas M. O'Non, in a field survey on Nov. 20, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 I-10: 1/4 Corner Common to Sections 26 and 27.
 G.L.O. Notes: Old Quarter Post per Resurvey by Wadsworth October 5, 1852
 Beech 4", N 73° W, 18 Links
 Lynn 6", N 77° E, 19 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 I-10: 1/4 Corner Common to Sections 26 and 27.
 Found 1/2" I.D. Iron Pipe
 4" & 6" Double Elm, N 15° W, 57.67'
 Power Pole, West, 32.56'
 Power Pole, S 18° E, 77.06'
 3.0' West of Centerline Donnybrook Road

APPROVED LAND CORNER
 P.A. 345 OF 1990
 LEELANAU COUNTY
 DATE: 10-30-96
 COUNTY REP. N.M. O'Non

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 I-10: 1/4 Corner Common to Sections 26 and 27
 1/2" I.D. Iron Pipe accepted as the best available evidence of the position of the original corner by the Leelanau Peer Review Group October 30, 1996. Replaced with a 3/4" I.D. by 3.0' long galvanized iron pipe with stamped brass cap set in a pavement box.
 Power Pole, West, 32.56'
 4" Elm SW of 6" Elm, N 15° W, 57.67'
 Power Pole, S 18° E, 77.06'
 Centerline Donnybrook Road, East, 3.0'

Signed by Nicholas M. O'Non
 Surveyor's Michigan License No. 28420

Date 12-30-96