

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF LEELANAU
RECEIVED FOR RECORD

1994 DEC 12 PM 1:41

Barbara Kirt
REGISTER OF DEEDS

#367

LIBER 2 PAGE 64

Register of Deeds Stamp & File Number

For corners in

Leelanau
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|---------------------------|-------------|
| 1. Public Land Survey | T <u>30N</u> R <u>12W</u> | <u>D-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Steven P. Bye, in a field survey on November 14, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

D-13: South 1/4 corner of Section 32
G.L.O. Notes "Set 1/4 section post"
Lynn 18 N 13 W, 36 links
Sugar 10 S 25 E, 22 links
County Surveyor notes: Stone "X" broken off, slight "s" on side.
6" ash S 54 W
4" ash N 73 15' E
8 black oak N 10 E

APPROVED LAND CORNER
P.A. 345 OF 1990
LEELANAU COUNTY

DATE: 9-7-94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

COUNTY REP. W. M. O'Neil

D-13: South 1/4 corner of Section 32
Found limestone with "X" broken off that fits L.C.R.C. File #270, Liber 1, Page 394 by Grier Jr.
Record witnesses:
8" ash N 37 W, 7.85'
12" ash S 54 W, 14.6'
10" ash S 83 E, 23.8'
18" oak N 12 E, 14.6'
5/8" rerod #19846 in concrete West 62.0' (North 1/4 corner Section 5, T29N, R12W)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13: South 1/4 corner of Section 32
Limestone accepted by the Leelanau County Remonumentation Peer Review group, September 7, 1994, and replaced with a 3/4" i.d. galvanized iron pipe 3' long with a brass cap.
8" ash N 37 W, 7.85'
12" ash S 54 W, 14.6'
10" ash S 83 E, 23.54'
18" oak N 12 E, 14.60'
5/8" rerod #19846 in concrete West 62.0'



Signed by Steven P. Bye

Date November 18, 1994

Surveyor's Michigan License No. 35991