

**SURVEY &  
REMONUMENTATION**

**MAR 15 2000**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

|                                    |                  |               |
|------------------------------------|------------------|---------------|
| <u>Leelanau</u><br>(County)        | Located In:      | Corner Code # |
|                                    | <u>T30N R12W</u> | <u>E-5</u>    |
| 1. Public Land Survey              | T___ R___        | _____         |
|                                    | T___ R___        | _____         |
|                                    | T___ R___        | _____         |
| 2. Property Controlling in Section | S___ T___ R___   | _____         |
|                                    | S___ T___ R___   | _____         |
| 3. Miscellaneous Property in Sec.  | S___ T___ R___   | _____         |
|                                    | S___ T___ R___   | _____         |

Barbara Kirt 12/30/99  
 Leelanau Reg of Deeds 3:34 pm  
 BJK Fee: 9.00  
 04B00002 P0361 Page 1 of 1  
 #664  
**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Nicholas M. O'Non, in a field survey on Dec. 22, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |    |   |    |   |    |   |    |   |    |   |    |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| A  | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |    |   |    | ● |    |   |    |   |    |   |    |   |
| 6  | 10 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |

A. Description of original monument and accessories and/or subsequent restoration:  
 E-5: Section Corner common to Sections 8, 9, 16 and 17.  
 G.L.O. Notes: Set post corner to Sections 8, 9, 16 and 17.  
 (Risdon, 1851) Beech 16", N 69° E, 56 Links  
 Beech 12", S 07° W, 6 Links  
 P.J. O'Non, 1956: Found Cedar Stake.  
 Gourdie Fraser & Assoc., 1975: Found iron.  
 N.M. O'Non, 1989: Found Concrete Monument.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 E-5: Section Corner common to Sections 8, 9, 16 and 17.  
 Found 4" diameter concrete monument.  
 (No old witnesses evident)

**APPROVED LAND CORNER  
 P. A. 345 OF 1990  
 LEELANAU COUNTY  
 DATE: 12-8-99  
 COUNTY REP. N.M. O'Non**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 E-5: Section Corner common to Sections 8, 19, 16 and 17.  
 4" diameter concrete monument accepted as the best available evidence of the position of the original corner by the Leelanau County Peer Review Group on December 8, 1999. Monument was considered to be a superior marker and was left in place.  
 15" Maple, S 85° W, 5.59'  
 9" Maple, S 05° W, 28.00'  
 20" Maple, S 60° E, 34.39'  
 18" Maple, N 20° E, 31.54'

Signed by Nicholas M. O'Non  
 Surveyor's Michigan License No. 28420

Date December 29, 1999

