

**SURVEY &
REMONUMENTATION**

MAR 15 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Leelanau</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>30N</u> R <u>12W</u>	<u>E-6</u>
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Barbara Kirt 12/30/99
Leelanau Rec of Deeds 3:35 PM
BJK Fee: 9.00
04800002 P0362 Page 1 of 1

#665

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Nicholas M. O'Non, in a field survey on Dec. 16, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17	●	16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-6: 1/4 Corner common to Sections 16 and 17.
G.L.O. Notes: Set 1/4 Post (Risdon, 1851)
Sugar 18", N 11° W, 12 Links
Sugar 14", N 76° E, 17 Links
H.R. Bruning, 1979: Found Cedar Stake
18" Beech, N 47°52' E, 10.2'
15" Maple, S 50°02' E, 38.9'
16" Maple, N 53°47' W, 38.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-6: 1/4 Corner common to Sections 16 and 17.
Found 4" diameter concrete monumnet
Spike in face of 24" Beech, N 50° E, 10.23'
22" Maple; N 06° E, 19.43'
19" Maple, S 09° W, 44.09'
15" Maple, S 23° E, 41.76'
In remnants of old East-West fenceline

**APPROVED LAND CORNER
P.A. 345 OF 1990
LEELANAU COUNTY**

DATE: 12-8-99
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6: 1/4 Corner common to Sections 16 and 17
Concrete monument accepted as the best available evidence of the position of the original corner by the Leelanau County Peer Review Group on December 8, 1999.
Monument was considered to be a superior marker and was left in place.
22" Maple, N 06° E, 19.43' Spike in face of 24" Beech, N 50° E, 10.23'
19" Maple, S 09° W, 44.09' In remnants of old East-West fenceline.
15" Maple, S 23° E, 41.76'
16" Maple, N 85° W, 44.62'

Signed by [Signature]
Surveyor's Michigan License No. 28420

Date December 29, 1999