

FEB 26 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Leelanau</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>30</u> N R <u>12</u> W	<u>E-9</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

Barbara Kirt 12/30/97  
 Leelanau Rec of Deeds 3:15 pm  
 BJK Fee: 9.00  
 04B00002 P0224 Page 1 of 1

#527

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, David T. Rowe, in a field survey on 12-15, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-9 Corner Common to Sections 20, 21, 28 and 29  
 G.L.O. notes: Set Post, Cedar 12" N70°E 49 lks., Sugar 14" S80°W 13 lks.  
 County Surveyor's Record: Book 3, pg.104 Cedar stake, 15" Elm N67° 15'W 70.2', 15" Elm N01°E 35.4' 5/8" x 24" iron bar set (N. O'Non 1971)  
 Iron Fd. (Bruning 1979, R.M. Harris 1981)  
 1/2" Rebar Fd. (DeLaMatar 1984) S. 24.78' 14" Poplar, S 25°W 14.60' 4" Poplar, S02°W 24.82' 18" Poplar  
 1/2" rerod Fd. (Mitchell 1987) E 16.96' 4" Cedar, N08°W 5.65' 4" Cedar, S23°W 14.65' 5" Poplar  
 1/2" rerod Fd. (N. O'Non 1993, 95, 96) Wit's match Mitchell.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-9 Corner Common to Section 20, 21, 28 and 29

Found 1/2" Iron Rod

APPROVED LAND CORNER  
 P.A. 345 OF 1990  
 LEELANAU COUNTY

DATE: 11-17-97  
 COUNTY REP. D.M. O'Neil

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-9 Corner Common to Section 20, 21, 28 and 29

1/2" iron rod accepted as the best available evidence of the position of the original corner by the Leelanau County Peer Review Group, 11-17-1997 and replaced with a 3/4" i.d. galvanized pipe 3' long with a brass cap.

Witnesses: S43°E 38.98' set nail in NE face of 6" Cedar  
 N19°E 23.36' set nail in E face of 8" Cedar  
 S58°W 37.66' set nail in NW face of 4" Elm  
 S06°E 24.80' Fd. spike in E face of 16" Aspen

Signed by David T. Rowe  
 Surveyor's Michigan License No. 11192

Date DEC 18, 1997

