

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF LEELANAU
RECEIVED FOR RECORD

1994 DEC 12 PM 1:41

For corners in

<u>Leelanau</u> <small>(County)</small>	Located In:	Corner Code ##
1. Public Land Survey	T <u>30N</u> R <u>12W</u>	<u>E-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Barbara Kist
REGISTER OF DEEDS

#365

LIBER 2 PAGE 62

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Steven P. Bye, in a field survey on November 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-12: East 1/4 corner of Section 32
G.L.O. notes "set 1/4 section post"
Beech 9 N 66 W, 50 links
Beech 16 S 34 E, 25 links
County Surveyors notes: Set iron pipe in stones
15" ash N 24 E, 23.0'
12" basswood S 57 30' E, 29.6'
14" elm S 41 30' W, 12.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-12: East 1/4 corner of Section 32
5/8" rerod with cap #6213 (Pierre O'Non) fitting L.C.R.C. File #100, Liber 1, Page 197 (Delameter)
Record witnesses:
28" ash N 24 E, 23.96'
20" ash S 56 25' E, 29.95'
8" maple S 84 30' W, 45.47'

APPROVED LAND CORNER
P.A. 345 OF 1990
LEELANAU COUNTY

DATE: 9-7-94
COUNTY REP. N.M.O.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-12: East 1/4 corner of Section 32
5/8" rerod with cap #6213 accepted by the Leelanau County Remonumentation Peer Review Group, September 7, 1994, and replaced with a 3/4" i.d. galvanized iron pipe 3' long with a brass cap.
28" ash N 24 E, 23.95'
10" maple West 45.47'
12" maple S 10 E, 13.88'
13" twin ash N 64 E, 35.20'

Signed by Steven P. Bye
Surveyor's Michigan License No. 35991

Date November 18, 1994

