

SURVEY & REMONUMENTATION

FEB 26 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Leelanau Reg of Deeds
EJK . Feet
04B00002 P0213
12/30/97
3:09 PM
9.00
Page 1 of 1

For corners in

| | | |
|------------------------------------|--------------------------|---------------|
| <u>Leelanau</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>30NR</u> <u>12W</u> | <u>G-9</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

#516
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

I, David T. Rowe, in a field survey on 12-9, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-9 Corner Common to Sections 21, 22, 27 and 28
- G.L.O. notes: 1851 Set Post Beech 18" N08°E 6 lks., Beech 8" S22°W 28 lks.
- County Surveyor's REcords: Iron Pipe
- 1/2" Rebar Set (Duane Wood 1977) S70°W 8.92' 14" Maple, N65°W 16.93 12" Oak, N25°W 25.88 3" Maple
- 1/2" iron w/cap (DeLaMater 1984) S18°W 8.28' 14" Maple N70°W 16.74 14" Oak, N18°W, 25.73 4" Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-9 Corner Common to Sections 21, 22, 27 and 28
- 1/2" iron w/cap #24625 on old fences N-S and W

APPROVED LAND CORNER
P.A. 345 OF 1990
LEELANAU COUNTY
DATE: 12-1-97
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-9 Corner Common to Sections 21, 22, 27 and 28
- 1/2" iron w/cap accepted as the best available evidence of the position of the original corner by the Leelanau County Peer Review Group, 12-1-1997 and replaced with a 3/4" i.d. galvanized iron pipe 3' long with a brass cap
- Witnesses: N19°W 8.25' Fd. nail in W face of 8" Maple
- N61°W 16.67' Set nail in SW face of 16" Oak
- S27°W 25.79' Fd. nail in W face of 14" Maple
- S77°E 21.12' Set nail in S face of a twin 5" Maple

Signed by David T. Rowe
Surveyor's Michigan License No. 11192

Date Dec 15, 1997

