

MAR 15 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Barbara Kirt 12/30/99
Leelanau Res of Deeds 3:37 pm
BJK Fee: 9.00
04800002 F0366 Page 1 of 1

For corners in

Leelanau
(County)

Located In:

Corner Code #

- 1. Public Land Survey T30N R12W K-5
 T R
 T R
 T R
- 2. Property Controlling S T R
 in Section S T R
- 3. Miscellaneous S T R
 Property in Sec. S T R

#669

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Nicholas M. O'Non in a field survey on Dec. 17, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- K-5: Section Corner common to Sections 11, 12, 13 and 14
 G.L.O. Notes: Set Post Corner to Sections 11, 12, 13 and 14 (Risdon, 1851)
 Beech 10", N48°E, 24 Links
 Beech 18", S43°W, 36 Links
- T.H. Weinert (1975): Found Iron
 30" Oak, S78°30'W, 24.74'
 8" Beech, S36°E, 8.48'
 12" Beech, N4°W, 17.56'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-5: Section Corner common to Sections 11, 12, 13 and 14.
 Found 5/8" iron rod w/cap no. 6213
 16" Beech, N02°W, 17.51'
 12" Beech, S35°E, 8.91'
 14" Ash, S15°W, 11.46'
 36" Oak, S80°W, 24.19'

APPROVED LAND CORNER
P. A. 345 OF 1990
LEELANAU COUNTY

DATE: 12-8-99
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-5: Section Corner common to Sections 11, 12, 13 and 14.
 5/8" iron rod w/cap no. 6213 accepted as the best available evidence of the position of the original corner by the Leelanau County Peer Review Group on December 8, 1999, and replaced by a 3/4" dia. by 36" long galvanized iron pipe with a stamped brass cap.
 16" Beech, N02°W, 17.51'
 12" Beech, S32°E, 8.85'
 14" Ash, S11°W, 11.46'
 36" Oak, S80°W, 24.21'
 In remnants of E-W fenceline.

Signed by [Signature]
Surveyor's Michigan License No. 28420

Date December 30, 1999

