

**MAR 15 2000**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Leelanau Located in: Corner Code #  
 (County)

1. Public Land Survey T30N R12W K-6  
 T\_\_\_ R\_\_\_  
 T\_\_\_ R\_\_\_  
 T\_\_\_ R\_\_\_

2. Property Controlling S\_\_\_ T\_\_\_ R\_\_\_  
 in Section S\_\_\_ T\_\_\_ R\_\_\_

3. Miscellaneous S\_\_\_ T\_\_\_ R\_\_\_  
 Property in Sec. S\_\_\_ T\_\_\_ R\_\_\_

Barbara Kirt 12/30/99  
 Leelanau Reg of Deeds 3:37 PM  
 BJK Fee: 9.00  
 04800002 P0367 Page 1 of 1

#670

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Nicholas M. O'Non in a field survey on Dec. 16, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |    |    |    |    |    |    |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

K-6: 1/4 Corner common to Sections 13 and 14.  
 G.L.O. Notes: Set 1/4 Section Post (Risdon 1851)  
 Beech 12", N37°E, 8 Links  
 Beech 10", S65°W, 46 Links

W.B.Batzer, 1972: Found 1" dia. iron bar at cor. of fences W & S.  
 L.C.R.C., Liber 1 Twin 30" Oak, N70°W, 7.27'  
 of Cor. Pages 69 10 Maple, N67°E, 41.81'  
 and 70. 8" W. Pine, N35½°W, 92.50'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-6: 1/4 Corner common to Sections 13 and 14  
 Found 1" dia. by 16" long iron bar  
 12" Beech, S74°W, 7.80'  
 9" Poplar, N23°W, 39.44'  
 7" Oak, N55°E, 16.35'  
 7" Maple, S26°E, 6.98'  
 At intersection of N-S & E-W Fencelines


**APPROVED LAND CORNER**  
**P.A. 345 OF 1990**  
**LEELANAU COUNTY**

DATE: 12-8-99  
 COUNTY REP. N.M.O'N

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6: 1/4 Corner Common to Sections 13 and 14  
 1" dia. by 16" long iron bar accepted as the best available evidence of the position of the original corner by the Leelanau County Peer Review Group on December 8, 1999.  
 Replaced by a 3/4" dia. by 36" long galvanized iron pipe with a stamped brass cap.  
 12" Beech, S74°W, 7.80'  
 9" Poplar, N23°W, 39.44'  
 7" Oak, N55°E, 16.35'  
 7" Maple, S26°E, 6.98'  
 At intersection of N-S and E-W Fences

Signed by Nicholas M. O'Non  
 Surveyor's Michigan License No. 28420



Date December 30, 1999