

**SURVEY &  
REMONUMENTATION**

**MAR 15 2000**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Barbara Kirt  
Res of Deeds  
BJK Feet  
12/30/99  
3:36 pm  
9.00  
04800002 P0365  
Page 1 of 1

For corners in

**SECTION**

Leelanau Located In: Corner Code #  
(County)

1. Public Land Survey T30N R 12W L-7  
T\_\_\_ R\_\_\_  
T\_\_\_ R\_\_\_  
T\_\_\_ R\_\_\_

2. Property Controlling S\_\_\_ T\_\_\_ R\_\_\_  
in Section S\_\_\_ T\_\_\_ R\_\_\_

3. Miscellaneous S\_\_\_ T\_\_\_ R\_\_\_  
Property in Sec. S\_\_\_ T\_\_\_ R\_\_\_

#668

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Nicholas M. O'Non, in a field survey on Dec. 16, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-7: 1/4 Corner common to Sections 13 and 24.  
G.L.O. Notes: Set 1/4 Section Post (Risdon, 1851)  
Sugar 30", S16°E, 8 Links  
Sugar 30", N57°W, 54 Links

H.H. Brehmer, 1940: Stone at Corner  
15" Maple, Approx. North, 28.4'  
12" Maple, N70°±E, 32.9'  
On Fenceline East and West  
2.0' W. of fenceline South

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-7: 1/4 Corner common to Sections 13 and 24  
Found 11"x6"x17" Blue Granite Stone  
28" Maple, N04°E, 28.82'  
20" Maple, N59°E, 46.61'  
7" Pine, S37°E, 26.14'  
7" Pine, N67°W, 13.91'  
5/8" iron rod w/cap no. 19846, N55°E, 0.71'

APPROVED LAND CORNER  
P.A. 345 OF 1990  
LEELANAU COUNTY  
DATE: 12-30-99  
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7: 1/4 Corner common to Sections 13 and 24  
Stone accepted as the best available evidence of the position of the original corner by the Leelanau County Peer Review Group on December 8, 1999, and replaced by a 3/4" dia. by 36" long galvanized iron pipe with a stamped brass cap.  
28" Maple, N04°E, 28.82'      14" Maple, N76°E, 31.92'  
20" Maple, N59°E, 46.61'      5/8" iron rod w/cap no. 19846,  
7" Pine, S37°E, 26.14'      N55°E, 0.71'  
7" Pine, N67°W, 13.91'      On fencelines East, West and North

Signed by [Signature]  
Surveyor's Michigan License No. 28420

Date December 30, 1999

